NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS.
2. FIGURED DIMENSIONS ONLY TO BE TAKEN FROM THIS DRAWING. ALL DIMENSIONS TO BE CHECKED ON SITE. ENGINEER TO BE INFORMED IMMEDIATELY OF ANY DISCREPANCIES BEFORE ANY WORK PROCEEDS.
3. REFER TO DRAWING **21208-DOW-0000** FOR PROJECT SPECIFICATION.

Pumping Appliance	
Overall Length	7.900m
Overall Width	2.500m
Overall Body Height	3.300m
Min Body Ground Clearance	0.150m
Track Width	2.500m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	7.750m

Rev	Date	Amendments	by	chkd
C05	26.10.23	BLUE LINE REMOVED	AG	AD
C04	21.09.23	SITE LAYOUT & AUTOTRACK REVISED	AG	AD
C03	03.04.23	BLUE LINE ADDED	AG	AD
C02	22.03.23	MINOR UPDATE	AG	AD
C01	08.03.23	AT - TENDER	AG	AD
P03	07.11.22	UPDATED AS PER ARCHITECT'S LAYOUT	AG	AD
P02	29.08.22	SWEPT PATH & RED LINE REVISED	AG	AD
P01	24.08.22	ISSUED FOR PLANNING	AG	AD

PROJECT

PROPOSED HOUSING DEVELOPMENT AT MAYESTON, POPPINTREE, DUBLIN 11

CLIENT

FINGAL COUNTY COUNCIL

DRAWING TITLE

PROPOSED SWEPT PATH ANALYSIS FIRE TENDER

drawn by: AG | date: 17.08.22 | scale: 1:250 @ A0 | chk: AD

21208 - DOW - 00 - XX-DR- C

Project | Originator | Volume | Level | Type | Role

DOW Project No.	drg. no.	rev.
21208	5007	C05

AP - PLANNING

Suitability Status: Code - Description

Cashel Business Centre,
Cashel Road, Kimmage, Dublin 12
T 01 4901611
E admin@downesassociates.ie
www.downesassociates.ie

Downes associates
Consulting Structural & Civil Engineers

THIS DRAWING IS COPYRIGHT