



GENERAL NOTES:

1. ALL DIMENSIONS AND LEVELS TO BE VERIFIED ON SITE PRIOR TO COMMENCEMENT OF THE WORKS. ANY DISCREPANCIES TO BE REPORTED TO THE ENGINEER.
2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE RELEVANT ARCHITECT'S AND OTHER CIVIL DRAWINGS.

LEGEND

- EXISTING WATERMAIN
- - - PROPOSED WATERMAIN 100mmØ (PE80)
- PROPOSED STOPOCK AND WATER METER BOUNDARY BOX
- ⊕ PROPOSED FIRE HYDRANT
- ⊗ PROPOSED SLUICE VALVE
- ⊕ PROPOSED MARKER POST & INDICATOR PLATE
- ⊗ PROPOSED SCOUR VALVE
- ⊕ PROPOSED AIR VALVE
- ⊗ PROPOSED THRUST BLOCK

WATERMAIN NOTES:

1. ALL WATERMANS AND SUPPLY SHOULD BE CONSTRUCTED TO IRISH WATER REQUIREMENTS AND IN ACCORDANCE WITH IRISH WATER CONNECTIONS & DEVELOPER SERVICES WATER INFRASTRUCTURE STANDARD DETAILS IW-CDS-5020-03 DECEMBER 2017.
2. THE CONTRACTOR SHOULD CONFIRM THE LOCATIONS OF ALL EXISTING WATERMAIN INFRASTRUCTURE ON SITE AND REPORT TO THE ENGINEER.
3. WATERMAIN PIPES SHOULD HAVE A MINIMUM NOMINAL PRESSURE CLASSIFICATION OF 10 BAR. MOPVC PRESSURE PIPES SHALL CONFORM TO UK WATER INDUSTRY SPECIFICATION NO 4-31-08 OR EQUIVALENT. MANUFACTURERS SHALL OPERATE A QUALITY SYSTEM IN COMPLIANCE WITH BS 5750 PART 2 (EN29002).
4. WATERMAIN PIPES SHOULD HAVE A MINIMUM COVER OF 900mm
5. AN APPROVED MARKER TAPE CONTAINING A TRACER WIRE SHOULD BE AFFIXED TO THE TOP SURFACE OF ALL WATERMANS
6. CONCRETE THRUST BLOCKS SHOULD BE PROVIDED ON WATERMANS AT DEAD ENDS, TEES, BENDS OF CURVATURE GREATER THAN 22 1/2° AND AT BOTH SIDES OF A SLUICE VALVE CHAMBER. ANCHOR BLOCKS SHOULD ENCASE THE PIPE IN CONCRETE (CLASS E, CLAUSE 1502, SPECIFICATION FOR ROADWORKS) TO A MINIMUM THICKNESS OF 150mm ALL ROUND AND SHOULD BE A MINIMUM LENGTH OF 750mm
7. SLUICE VALVES SHOULD COMPLY WITH THE REQUIREMENTS OF BS 5163. THE DEPTH OF THE SLUICE VALVE SPINDLE CAP BELOW FINISHED GROUND LEVEL SHOULD NOT EXCEED 300mm
8. HYDRANTS SHOULD BE OF THE MALE THREAD SCREW DOWN TYPE IN COMPLIANCE WITH THE REQUIREMENTS OF BS 750. HYDRANT OUTLETS SHOULD COMPLY WITH THE CHIEF FIRE OFFICERS REQUIREMENTS. THE DEPTH OF THE HYDRANT OUTLET BELOW FINISHED GROUND LEVEL SHOULD NOT EXCEED 200mm
9. SCOUR VALVES TO BE LOCATED AT LOW POINTS AND AIR VALVES AT HIGH POINTS ALONG THE VERTICAL PROFILE OF THE WATERMAIN. CONTRACTOR TO AGREE SPECIFICATION FOR VALVES WITH FINGAL COUNTY COUNCIL.

B	02.08.19	SITE LAYOUT REVISED-UNITS ALTERED	JM MK
A	22.07.19	CHANGES AFTER INITIAL COMMENTS	JM MK
REV	DATE	DESCRIPTION	BY

DRAWING STATUS:
PART_8_PLANNING

CLIENT:
FINGAL COUNTY COUNCIL

JOB DESCRIPTION:
CAPPAGHFINN PHASE III HD

DRAWING TITLE:
WATERMAIN LAYOUT

PROJECT No.:	DRAWING No.:
P-3333	C-04
SCALE:	REV. No.:
1:500	B

DATE:	25.06.19
DRAWN BY:	PMCG
CHECKED BY:	MK
APPROVED BY:	PMCM

McMahon Associates
Consulting Civil & Structural Engineers, Project Managers
Environmental Engineers, PSDP & Traffic Engineers
The Mill Building, Newtown Link Road, Greenhills, Drogheda, Co. Louth
t: 041 2137 050 e: info@mcMahonengineers.com