SCHEDULE OF TYPICAL TREE PLANTING

Single stemmed tree

Multi-stemmed tree

34 no. Ag — *Alnus glutinosa* 3 x tr., wrb. 4-5m h., 14-16cm g., feathered.

27 no. Sc — *Salix caprea* 3 x tr., wrb. 3m h. multistem

29 no. Sf — *Salix fragilis* 3 x tr., wrb. 3m h. multistem

16 no. Qr — *Quercus robur* 4 x tr., wrb., 4-5m h., 18-20cm g., clear stem min. 2.2m

10 no. Bp — *Betula pendula* 3 str., wrb., 12-14cm g., 3 m h., feathered

5 no. Ps — *Pinus sylvestris* 3 x tr., wrb., 30-35cm g., 4-5m h., clear stem min 1.8m

8 no. Py — *Prunus yedoensis* 14-16 cm g. 4 x tr., wrb., 3.5m h., clear stem min. 1.8m.

28 no. Tc — *Tilia cordata 'Greenspire'* 4 x tr., wrb., 4m h.,16-18cm g., clear stem min. 2.2m

6 no. Pc — *Pyrus calleryana 'Chanticleer'* 3 x tr., wrb., 3m h., 12-14 cm g., feathered

**SCHEDULE OF TYPICAL PLANTING**

GROUNDCOVER AND HERBACEOUS MIX, TYPICALLY:

*Dianella nigra* 2 ltr cg.
*Dryopteris filix-mas* 2 ltr cg.
*Convallaria majalis* 2 ltr cg.
*Geranium* spp. 2 ltr cg.
*Helleborus foetidus* 2 ltr cg.
*Luzula sylvatica* 2 ltr cg.
*Luzula nivea* 2 ltr cg.
*Echinacea purpurea* 2 ltr cg.
*Hemerocallis* sp. 2 ltr cg.
*Hyacinthoides* spp. 2 ltr cg.
*Narcissus* spp. 2 ltr cg.
*Pulmonaria officinalis* 2 ltr cg.
*Verbena bonariensis* 2 ltr cg.

HEDGE AND SHRUB PLANTING, TYPICALLY:

*Crataegus monogyna*: 600-900mm h.
*Carpinus betulus*: 900-1200mm h.
*Buxus sempervirens*, 2 ltr. cg.

Planted at 450mm centres in single rows and 600mm centres in double staggered rows.

**Abbreviations:**

| | |
|---|---|
| xtr. | number of transplants in nursery |
| h. | height |
| s. | spread |
| wrb. | wire root-balled |
| cm g. | girth of tree in centimeters measured 1m above ground |
| 2 ltr. cg. | plants supplied in 2 litre volume containers |

**SCHEDULE OF PROPOSED PLAY EQUIPMENT**

**DESTINATION PLAY**

| REF. | QUANTITY | DESCRIPTION |
|---|---|---|
| P1 | 1 | Destination play structure with multiple play values. |

**NATURAL PLAY TRAIL**

| REF. | QUANTITY | DESCRIPTION |
|---|---|---|
| P2 | 3 | Twin balance beam |
| P3 | 2 | Balance beam |
| P4 | 2 | Zigzag Stepper |
| P5 | 8 | Jumping disks |
| P6 | 40 | Vertical stepping logs |
| P7 | 1 | Totter beam |

**NATURAL PLAY SLIDE**

| REF. | QUANTITY | DESCRIPTION |
|---|---|---|
| P8 | 1 | Large slide integrated into mound. |

**NATURAL PLAY HILL AGES 5-12**

| REF. | QUANTITY | DESCRIPTION |
|---|---|---|
| P9 | N/A | Climbing boulders |
| P10 | N/A | Climbing steps |
| P11 | 2 | Climbing ropes |
| P12 | 1 | Climbing net |

**LEGEND AND SCHEDULE OF MATERIALS**

- PLANNING APPLICATION BOUNDARY
- PROPOSED PAVING AT THRESHOLDS
- PROPOSED SELECTED DECORATIVE CONCRETE FINISHES
- PROPOSED SELECTED SELF BINDING AGGREGATE
- PROPOSED SELECTED BOARDWALK
- PROPOSED SELECTED SOFT FALL SAFETY SURFACES
- PROPOSED SEATING ELEMENTS
- PROPOSED TOPOGRAPHY MOUNDING
- PROPOSED MODIFIED TOPOGRAPHY
- EXISTING LEVEL RETAINED
- PROPOSED EMERGENT WOODLAND
- PROPOSED LAWN
- PROPOSED MIXED LAWN & STONE PAVING
- PROPOSED INFORMAL MOWN GRASS PATHWAYS
- PROPOSED RANDOM FORMAT RECYCLED PAVING
- PROPOSED SWALE/ SWALE LIKE PLANTING
- PROPOSED MARGINAL PLANTING
- PROPOSED NATURAL PLAY (CLIMBING HILL)
- PROPOSED PLAY ELEMENTS
- PROPOSED TREES REFER TO PLANTING SCHEDULE
- PROPOSED PUBLIC LIGHTING
- PROPOSED LOW RISE BARRIER INDICATING EMERGING WOODLAND BEYOND
- PROPOSED NORTHERN BOUNDARY FENCE
- PROPOSED SECURITY BOLLARDS
- LANDSCAPE DETAIL AREAS REFER TO DRAWINGS 2100/2101

This drawing is the copyright of the Landscape Architect. Unless otherwise stated all dimensions are in millimetres. Where dimensions are not given, drawings must not be scaled and the 'matter must' se referred to the Landscape Architect. If the drawing includes conflicting details/dimensions the matter must be referred to the Landscape A chitect. All dimensions must be checked on site. The Landscape Architect must be informed, by the Contractor, of any discrepencies before work proceeds.

**NOTES:**

| DATE | REV. | DESCRIPTION | DRAWN BY | CHECKED BY |
|---|---|---|---|---|
| 14.10.2021 | A | Addition of new footpaths. Attenuation incorporated into the wetland to the west of the scheme. Southern boundary by copies of trees amended. | th | df |
| 20.10.2021 | B | Schedule of proposec planting included. Schecule of proposed day included. Beyond boundary proposals omitted. | th | df |
| 26.10.2021 | C | Schedule of materials revised. Detail areas indicated on plan. | th | df |
| 08.12.2021 | D | Title block rerised. | th | df |

DERMOT FOLEY LANDSCAPE ARCHITECTS
NAUPAS STREET, BLACKPITTS, D08 DD56 IRELAND
T +353 1 4545148 WWW.DERMOTFOLEY.COM

**CLIENT:** FINGAL COUNTY COUNCIL

**PROJECT:** PART X\ CHURCH FIELDS HOUSING AND EASTERN LINEAR PARK DEVELOPMENT

**DRAWING:** LANDSCAPE PLAN

**ISSUE STATUS:** PLANNING

| DRAWING NO. | REVISION |
|---|---|
| Fc.01-DR-2002 | D |

| PROJECT NO | SCALE | SHEET SIZE | DRAWN BY | CHECKED BY | 1st ISSUE |
|---|---|---|---|---|---|
| Fc.01 | 1:500 | A1+ | th | df | 01.10.2021 |

NORTH

APR 26 09:45:45 2019 P:\FC\01\DR\2002.dwg